



Duchesne County Road Department Is Seeking RFB for a Bedrock Roads, LithTec Project to be Performed on Two County Roads Within Duchesne County.

3275 West from 9000 North And 1000 West From 9000 North.

Contractor Scope, 3275 West CR#165: Approximately 1.8 centerline miles 22' wide road surface on 3275 West going Southbound from 9000 North. 198000 SQ feet,

- Mobilization.
- Pulverizing existing road 10" or + deep (Asphalt thickness may vary).
- Provide spreader truck for LithTec distribution.
- Blending equipment for a 3% LithTec treated material 8" deep to Bedrock Roads specs.
- Provide ground labor and or equipment to load 60 tote sacks into spreader truck.

Contractor Scope, 1000 West CR#176: Approximately 2.25 centerline miles 22' wide road surface on 1000 West going Southbound from 9000 North. 264000 SQ feet,

- Mobilization from 3275 West to 1000 West (approximately 2.25 miles).
- Pulverizing existing road 10" or + deep (asphalt thickness may vary).
- Provide spreader truck for LithTec distribution.
- Blending equipment for a 3% LithTec treated material 8" deep to Bedrock Roads specs.
- Provide ground labor and or equipment to load 124 tote sacks into spreader truck.

Duchesne Counties Scope for 3275 West & 1000 West: Duchesne County Road Department will provide the following items and equipment to the total project:

- Traffic control and flagger operation if needed.
- Motor graders and labor for road profiling and finish grade of roadway.
- 25,000 pounds of sheep foot roller, and also a pneumatic roller and labor.
- Tail handler or fork lift and labor to unload tote sacks from trucks and assist loading of spreader truck.
- Duchesne County to provide Bedrock LithTec product including re-surfacing of roadway.

Contractors shall provide in sealed RFB bid packet to Duchesne County copies of in force insurance policies for liability for \$1,000,000.00 and in-force copies of workers compensation insurance.

All of Contractor's workers, while working on the project, shall wear all required PPE's, including ANSI type III vests, steel toe boots, ANSI approved hard hats, including any other required OSHA safety gear or equipment and any factory installed equipment guards. Contractor shall ensure that all equipment in the work zone be equipped with working, flashing lights and applicable placards.

All bids need to be delivered to the Duchesne County Road Department at **20800 West East River Road, Duchesne Utah 84021**, no later than 4:00 PM April 16th 2020. in sealed envelope with project name and contractor information clearly printed on the front of envelope. **The Duchesne County Commission will open and consider all bids presented on Monday April 20th at 9:00 AM in regularly held commission meeting. All RFB's shall be signed by Contractor in sealed bid packet. Duchesne County will return a signed copy of RFP to Contractor upon acceptance of bid by County Commission.**

Duchesne County reserves the right to reject any and all bids that do not meet the RFB requirements. Duchesne County reserves the right to not award bids at its discretion for any reason allowed by law.

Project start dates are yet to be determined. Projected dates are estimated to be sometime in late May to mid-June, 2020, with projected completion dates estimated to be no later than July 15th, 2020.

_____	_____ 2020
Contractor Signature	Date

_____	_____ 2020
Duchesne County Commission (Chair)	Date